160 - 92

P34

G. R. S. IX-5]

*Previous references.* 1884-85

191 .

( Mun. )

File No. 15-84

Serial Nos.

*Later references.*

# GENERAL AND REVENUE SECRETARIAT.

---

*Serial Nos.*

M ~~Part~~ B for Oct. 89

---

SUBJECT.

~~Production Board~~ Lighting and water Supply to The town of Davanagere.

---

From The Deputy Commissioner
Shimoga Dt

To The Secretary to the ~~Chief Commissioner~~ Dewan
of Mysore, Revenue Department

Dated 4th
Despatched 7 October
Received

Enclosures No. –

General No. 797
R No. 598 } 1884-85.

States having held a meeting of the Municipal Board at Davangere & requests sanction to the resolutions about lighting and water supply to the Town.

BRK
10/10/84

(2)

No 197 } 1884-8.
1598.

Shimoga District
Deputy Commrs Office
Camp Channagiri 4th October 1884
Dated 7th "

To

The Secretary to the
Dewan of Mysore
Revenue Deptt

Sir

I have the honor to state that on my visit to Honnegere I held a meeting of the Municipal Board. when the Budget was submitted to the Board for approval.

Two resolutions were brought forward which will entail a small extra expenditure but as the expenditure is unavoidable, I request that it may be sanctioned.

The first resolution is a provision for the lighting of the town. Lamps and posts to have been provided but no provision was made for oil &c. I now

recommend that the expenditure of Rs.144 or 1 per lamp be sanctioned. This for the remaining months of the official year will come to Rs. 72—"—"

The next proposal was to raise the pay of the Municipal Sweepers from 3 Rs to 4 Rs a man. This will involve an extra expenditure of Rs 60 for the remainder of the official year i.e. Rs 10 per mensem. But as the men will not work on the present pay and as all the members assure one that they pay here Rs 4 or 5 a month for a private coolie, the increase appears to be absolutely necessary.

Even with this increased expenditure there still remains to the balance of the Municipality Rs. 6056—4. All the members and the Amildar urged strongly

on me the necessity of spending this money in improving the supply of water for the town. This appears to me to be most urgent as a water famine is threatened, and I therefore request sanction to the scheme estimate for which will be prepared and submitted forthwith.

As if rain does not fall within the next ten days, it will be necessary to begin this work. I have directed the Guildar to commence the work in anticipation of sanction. Should there therefore be any objection to the scheme, I request it may be kindly communicated to me forthwith so that the work may be stopped.

I have the honor to be
Sir
Your most obedt. Servt.

[illegible]

[illegible] For Deputy Commr.

(5) Read. (2)

Letter from the Dy Commr Shemoga dated 4th October 1884 No 791/598

No 4131-2/232 dy 16 10 84

Order thereon

In the above letter it is proposed to incur Expenditure on account of Lighting 12 Lamps at the rate of 1 Rupee per Lamp per mensem and to increase the pay of 10 Sweepers from Rs 3 to 4 each per mensem in the town of Davangere This proposal, which involves an Extra Expenditure of Rs 72 ~~on account~~ for Lighting and ~~RS~~ to be under the head Conservancy, for the latter half of the current Official Year is sanctioned.

2 The Dy Commr reports that ~~Excess~~ allowing for the above increase of Expenditure there will remain at the credit of the Municipality of Davangere, a balance

of Rs 6056 - 4 which the Members of the Municipal Board including the Amildar propose to expend on improving the supply of water for the town. This work is no doubt important; but the whole of the available balance cannot, without prejudice to general municipal interests be appropriated for it. About two-thirds of the balance or Rs 4000 can be spent on the improvement of water supply for the town. Estimates and Notifications for the various works proposed to be carried out under this head being submitted in the usual course

Secretary

The Deputy Commissioner
Shimoga District
Comptroller

BRK
3-1cq

9.

(General Serial No 29)

1884.

From

The Deputy Commissioner

To

Shimoga District

The Secretary to the Chief Commissioner Dewan
of Mysore, Revenue Department.

Dated 31st October -

Despatched

Received

Enclosures No 3

General No. 896 } 1884-85.
R No. 666.

Sir

With reference to the Dewan's Proceedings no: 4131-2/232 of the 16th instant approving of the proposal for increasing the water supply of the Davangere town by sinking a Honda I have the honour to forward herewith for early sanction an estimate and plans amounting to Rs 4,700/- framed by the Executive Engineer together with copy of

(8)

his letter no: 602 of the 26th Instant:

2 I beg to draw attention to para 2 of the letter from which it would appear that the Brindar has sunk a well at his own cost for the use of the townspeople this seems to be deserving of commendation

I have the honor to be

Sir,

Your most Obedt servant

H. Mackay

Depty Commissioner

(9)

Estimate No. of 1884-85

Kowalli Range.

Shemoga Division

Mysore P. Works Department.

Estimate of the probable cost of Constructing a Standa at Davengere.

References.

Dy Commissioners Inspection Report on Davengere town dated 3d October 1884

Dy Commrs No 224 of 4: October/84 to the Executive Engineer, Shemoga division

Executive Engineers No 1961 of 6: October/84 to the Assistant Engineer, Kowalli Range

Report.

Davengere is a large Commercial town which was visited a population of 6201 and contains 1501 houses. There are about 250 private wells had very little in use. The supply is dispensed all about. Notwithstanding about 2664 of the population resort to the tank situated to the West of the town, having but a catchment area of 781 acres, which is not capable of being increased by feeder Channels. The tank is generally empty for 2 or 3 months in a year, during which time great difficulty is felt by the resorters to the tank.

As per statement furnished by the ancildar Alt 26/10/84

In the year of average rainfall Alt 26/10/84

At the urgent requisition of the Deputy Commissioner this Estimate is framed

With his various memos dated 26/10/84 & his Remarks thereon

Soon. L

framed to Construct a Nonda at the right end. The work proposed consists of sinking a rectangular well 20×15 yards to a depth of 42 feet, sloping off the top 6 feet, revetting the same with big stones in steps of 2 ft height & offsets of 1 foot width; constructing a flight of steps and enclosing the well with a bund 9 ft high revetted inside for 7 ft, 20 ft clear from the well.

3 From the wells close to the site selected & two temporary wells sunk in the bed of the tank, it is found that soil 5 to 6 ft at top consists of hard earth, and soft rock below and that good springs of portable water are met with at depths of 35 to 40 feet.

S. B. Ray Draughtsman &c

Assistant Engineer
Nowmalli Range

S. Vaguvalu
Executive Engineer
Tumkur Division

Camp
Tumkur
27th October 1891

timate for Constructing a Hondu in the bed of Dowengere Lauk.

(11)

| Details of work. | No. | Dimensions L. B. D. | | | Quantities | |
|---|---|---|---|---|---|---|
| Earth work cutting through Soft Stone, a rectangular well. | | | | | Yards. | |
| 1st Tier — well | 1 | 21 | 20 | 15 2 | 600 | Cyds |
| Steps | 1 | 25½ | 4 | 2 | 204 | 804 |
| 2nd Tier — well | 1 | 20 | 15 | 2 | 600 | |
| Steps | 1 | 22 | 4 | 2 | 176 | 776 |
| 3rd Tier — well | 1 | 20 | 15 | 2 | 600 | |
| Steps | 1 | 19 | 4 | 2 | 152 | 752 |
| 4th Tier — well | 1 | 20 | 15 | 2 | 600 | |
| Steps | 1 | 15 | 4 | 2 | 120 | 720 |
| 5th Tier — well | 1 | 20 | 15 | 2 | 600 | |
| Steps | 1 | 11½ | 4 | 2 | 92 | 692 |
| 6th Tier — well | 1 | 20 | 15 | 2 | 600 | |
| Steps | 1 | 7⅓ | 4 | 2 | 61 | 661 |
| 7th Tier — well | 1 | 20 | 15 | 2 | 600 | |
| Steps | 1 | 3 | 4 | 2 | 24 | 624 |
| Sloping the top Steps at ½ to 1 | 1 | 70 | $\frac{5\frac{1}{2}}{3}$ | $\frac{7}{3}$ | 300 | Cyds. |
| — Do — Sides of steps | 1 | $\frac{164}{3}$ | $\frac{5\frac{1}{2}}{3}$ | $\frac{7}{3}$ | 234 | 534 |
| Roughstone work. | | | | | | |
| Revetting in 3 Steps of 2' height and 1 foot offset | | $\{(2\times(50+65)-14)4\times6$ | | | | |
| | | | | 27 | 192 | " Cyds |
| Sides of steps | | $3\times79\times4\times6$ | | | | |
| | | | | 27 | 141 | 333 |
| Height of Steps | 1 | $\frac{91}{3}$ | $\frac{15}{3}$ | $\frac{4}{3}$ | 202 | 202 |
| Revetting the mound enclosing the well including steps | 2 | $(\frac{176\frac{1}{2}+113}{3})\frac{3}{4}\times3$ | | | 434 | Cyds 434 |
| Baling water. — Lump Sum | | | | | | Rs. 50 |

# Abstract.

| Items of work. | Per | Rate | Quantity | Cost. |
|---|---|---|---|---|
| Earth work cutting thro' soft rock 1' ter- | Cyd. | " 2 6 | 804 | 126 |
| Do Do 2' | " | " 4 " | 776 | 194 |
| Do Do 3' | " | " 6 " | 752 | 282 |
| Do Do 4' | " | " 9 " | 720 | 405 |
| Do Do 5" | " | " 13 " | 692 | 562 |
| Do Do 6' | " | 1 2 " | 661 | 744 |
| Do Do 7' | " | 1 8 " | 624 | 936 |
| Sloping the top for steps | " | " 2 6 | 534 | 83 |
| Roughstone work. | " | 1 4 " | 333 | 416 |
| Height of steps. | " | 1 12 " | 202 | 354 |
| Revetting the hind face | " | " 12 " | 434 | 325 |
| Baling waters | Lump Sum | | | 50 |
| | Total Rupees | | | 4,477 |
| Contingencies @ 5 per cent. | | | | 223 |
| | Grand Total | | | 4,700 |

Angode.
21st Oct/84.

(Sd) B. P. Raghavalu Naidu.
Asstt Engineer,
Hunnalli Range.

No. 602

From

The Executive Engineer
Shimoga division

To The Deputy Commissioner
Shimoga district

Sir,

With reference to your docket No. 224 dated 4th October and reminder No. 255 dated 16th Instant, I have the honor to forward herewith plan and estimate amounting to Rs. 4,700 for sinking a Honda at Hanevgre.

2. I inspected the spot in company of the Amildar and the Municipal members on the 18th October, and was quite satisfied as to the necessity of sinking a Honda. The Amildar has sunk a well in the bed of the tank at his own cost. It contains water at a depth of 25 ft. It is situated in the hollow of the tank, and must silt up the next time the tank fills.

is not equal to the demand.

3. I approve of the site shown to me. It is on the right extremity of the tank and close to the town. At first the Municipal member wanted it of a size four times as large as now estimated for. When they were explained the objectionably large cost it would entail, they consented to the size now fixed, viz, 20 x 15 yards.

For a large town like Manengere the size of 20 x 15 Yds is, in my opinion, absolutely necessary, as, without a large collecting basin and copious springs, the supply of water during times of drought cannot be equal to the demand. More than 1/3 of the town will be dependent on the Handa.

5. It is not possible to increase the drainage area of the tank by cutting a supply channel. The tank runs dry for 3 months in ordinary years and six months

in the years of drought.

6. The design of the Honda has met with the approval of the Municipal members. The soil being rocky, the sides will be left vertical, and only the top 6 feet will be revetted. The spoil from the excavation will be thrown in the shape of a bund all round to exclude the water of the tank and the surface drainage of the town.

7. Not being acquainted with rates for this sort of work in the locality, I asked the Municipal members some of whom have sunk large wells costing 3 to 6 thousand rupees in the vicinity of Ratnagiri. They could not give me any definite information on the point. I explained to them the rates put down by me and the probable amount the Honda was estimated

to cost, and they expressed that the pronuncon was reasonable.

Shane dea

Signed / A. S. Chaswakar
Executive Engineer
Shimoga Division

Camp Anjoda
26 October 1884
30 " do

"True copy"

G B Mulgoh

Deputy Commissioner
Shimoga Dt.

(General Serial No. 31.)

1884.

*From*

*To* The Deputy Commr
Shemoga Dist.
& Comptroller.

*Dated* 16th October

*Despatched*

*Received*

**Enclosures No.**

*General No.* 4131-A
*No.* 232

Conveying sanction to the proposal made by the Davangere Municipality for lighting 12 Lamps at the rate of 1 Rupee per Lamp ~~per~~ & for increasing the pay of ~~the~~ 10 Sweepers from Rs 3 to 4 each per mensem & requesting the Dy Comm to submit full details in connection with the water supply of the town.

Read:—

(17)

Shimoga Dy Com's
No. 896/666 dated 31st October 1884,
submitting an Estimate costing
Rs 4700 for constructing a
Honda in the bed of the
Davangere Tank.

---

No. 4711-12/261 of 12-11-84

Order thereon

The Estimate, receive
with the above amounting
to Rs 4700 is sanctioned.
The charge will, as proposed
by the Dy Comr in his No.
797/598 dated 4th October 1884, be
treated as an addition to the
current year's Budget grant
and met from the Balance
available at the credit of the
Municipality of Davangere

mmk
15-84
L

+ Copy of the abstract Estimate to be made out

To
The Dy Comr Shimoga District
returning the Estimate and Plan
together with C. E. report in original—

+ Comptroller with copy of abstract Estimate.

[NB. Copy of the Estimate

(General Serial No 31.)

1884.

From 1594.

To The Rt Hon. Sir Thomas Thompson
Lieutenant Governor

Dated 12th March

Patched

Inked

Enclosures No. 3
1.

No 4711 42

No 11428 9152

Submitted
C. Macdonald

Sanctions extension for
Contracting a Treaty a
the Rt the Rt Hon. Governor

(General Serial No. 29.)

1886

OFFICE OF THE
887
BANGALORE

From The Deputy Commissioner
Shimoga Dt.

To The Chief Secretary to the Dewan of Mysore.

Dated 9th March

Despatched

Received

Enclosures No. 2

General No. 1140 } 1885-86.
No. 912

Sir

With reference to the Dewan's Pro. No. 4711-12/261 of the 12th November 1884 sanctioning an estimate amounting to Rs 4700 for sinking a Bonda at Davengere, I have the honor to state that in the course of execution of the work some alterations having been found necessary the Executive Engineer has prepared a revised Est and plan which bring

down the cost to Rs 4103. The estimate and pla
are herewith forwarded for sanction.

2. I have seen the Honda in person
A sum of Rs 1371-15-- has been spent on it
the Taluk authorities, but further progre
has been arrested by the Honda being fu
What remains to be done consists of wor
requiring professional skill, I would recom
mend that the work may be handed
over to the P. W. D for execution the
funds being supplied by the Municipalit

3. I apprehend that if the work is left
to the unskilled and slovenly hands of the
Municipal agency what now promises t
be a good source of water supply will
share the fate of the Bowdi in the bed
of the Kodakere tank at Tirupore.

I have the honor to be
Sir
Your most obedt. Servt.

V P Madhavarao
Deputy Commissioner
Shimoga D t.

DRG.

(General Serial No. 31.)

21

188

From Read

Letter No. 1140/912 of 19 March 1886 from the Superintending Engineer Dindigul District recommending that the remaining portion of the Road work at Damaycore be carried out by the P.W.D. professional skill being considered necessary

To

Dated

Despatched

Received

Enclosures No.

General No.

No.

Letter No 1140/912 of 19-3-86 from Shemoga with 2 Enclos.

No 4711-12/261 of 12-11-84 to do & Compts

No 896/666 of 31-10-84 from Shemoga Encls 3.

413-2/232 of 16-10-84 to do & Compts

797/598 of 4-10-84 from Shemoga

Rupees 18/6

(22)

Get the papers from the P.W.D. 5/6

Lawrence 5/7

Lawrence Bowring 7/89

(General Serial No. 21)

1889.

1967

96

From The Deputy Commissioner Chitaldrug District

To The Chief Secretary to the ~~Durbar~~ Govt. of Mysore.

Dated 15th June 189.

Despatched

Received

Enclosures No. one.

General No. 104.

No. 97.

Section Genl

No 15-K

Serial No. 7

In the year 1884 the then Deputy Commissioner Mr Bricklejohn of the Chitaldrug District to which the Taluk of Davengeri then stood attached recommended the Construction of a Bunda (or pond) at Davengeri from Municipal funds for the benefit of the people of that place.

2.— Accordingly an Estimate for 4700 Rs: was sanctioned in Pro: No. 4711-4/261 of the 12th November 1884.

3.— In 1886 (after some portion of the work had been executed) a revised Estimate reducing the amount from 4700 Rs: to 4103 Rs: was prepared

(13)

And submitted for sanction with the Shemoga Commissioner's letter ——— No. 1140/912 of the 19th March 1886. It was suggested at the time that as the work required professional super- it might be transferred to the P.W. Department for execution, the Municipality affording funds.

4. — The proposal was sanctioned in Pro: No. 7425-300 of the 29th March/86 and the work transferred to the P.W. department.

5. — The Executive Engineer has now again revis the Estimate raising the Amount to 5880 Rs:, on the ground that owing to the Railway works hig rates have necessarily to be given. I have with submit the re-revised Estimate for sanctio

6. — I have seen the Honda. It is a very usef and necessary work as being the Chief (if n the only) source of drinking water supply t the thickly populated town of Davengere. A sum of 1000 Rs: has been provided in the Current years Municipal budget for Expenditure on this work during the yea

I have the honor to be
Sir
Your most obedient Servan

Deputy Commissioner
Chitaldrug Distt:

(24)

Section Menl
15-889
Serial No 18

Read —

(16)

Letter from the Dy Comr Chittaldroog Division, dtd 10/93 dated 15th June 1889. Submitting for preference & Certificate for Rs 5'880 for the construction of a Honda (or ford) in the Municipality of Davangere

(2) Also Dewan's Proc dtd 11-120/261 and 425-26/300 dated 12th November 1884 and 29th March 1886 respectively

Order thereon 32234/79 31st July 1889

The Estimate for Rs 5'880 referred to in the above is Sanctioned To meet the charge, which is debitable to the municipal funds of the town of Davangere the provision of Rs 1000 made under "VIII P W (f) Water Supply" in the current year's Budget of the town, will as proposed, be appropria

in the present year The
Dy Comr: is however
requested to state what
amount has already
been spent upon the
work ~~from time to time~~ up to date.

Under Secretary
Chattahoochee

To.
The Dy Comr: Engr Dept.
Referring the Estimate
" Comptroller with abstract
Estimate
N.B. [Copy of the Estimate to be
retained for office use]
N.B [Do attend under Chief Secy's orders]

(General Serial No. 31.) (57)

188

OFFICE OF THE
14 AUG 89
DEWAN OF MYSORE

26

From

The Deputy Commissioner
Chitaldrug

To The Chief Secretary to the ~~Dewan~~ Government of Mysore

Section — Revenue
" 15. Aug
" 1
Serial No.

3950 of 1889

Dated 5th August 1889
Despatched 6th do
Received

Enclosures No. None

General No. 174
No. 163

With reference to Government Proceedings No 3223-4 of the 31st ult-imo sanctioning the re-revised Estimate for Rs 5880/- for the Honda at Davangére Town, has the honor to state that a sum of Rs 3154/- was spent on it upto the end of May 1889. No work was done since May pending sanction to the revised Estimate.

File
13/8

Office
13/8 Sir
Papers received
and sanctioned
Honorary
Salaries
Viewed in the
the amount

Read

Docket from the Dy Comr Chittaldroog Dated 5th August 1889 etc 4174 stating that a sum of Rs 3154 was spent on the Honda in the Davengere Municipality, for which a revised Estimate of Rs 5880 was sanctioned in Pro etc 3223 4-47 31st July 1880 79 Order thereon C.No 3950 of 18 August 96 22 1/2

Recorded.

To.

Under Secretary

The Dy Comr Chittaldroog Dist

(General Serial No 30.)

10

1889.

*From* The Chief Secretary

*To* The Lt Colonial Chief J

*Dated* August 1889

*Despatched*

*Received*

**Enclosures No.**

*General No.*

*No.*

(General Serial No. 31.)

1889

OFFICE OF THE
5278
11 OCT. 89
284
DEWAN OF MYSORE.

From

The Deputy Commissioner
Chitaldroog Dist

To The Chief Secretary to the ~~Dewan~~ Govt of Mysore.

Dated 2nd October 1889

Despatched

Received

Enclosures No. Nil

General No. 271

No. 257

Subject Government Proceedings No 3223-4 of the 31st July 1889 sanctioning the Estimate for Rs. 5880 for sinking a Honda at Davangere.

---

Has the honor to state that in the current Year's Municipal Budget of the Town of Davangere only ~~Rs.~~ 1000 have been provided for the work but in his docket No: 569 of today the Executive Engineer says that as it

(30) will be completed this year the whole of the sanctioned amount will be required. Up to the close of last year Rs 2,"27.7 was spent on it and so the whole of the remaining sum of Rs: 3152-8-, will be required for Expenditure this year. Begs therefore that the provision of Rs 1000 may be raised to Rs. 3152-8-, the excess amount being met out of the accumulated balance at the credit of the Municipality, which at the beginning of the current year was Rs 6616-3-2.

I have the honour to be

Sir

Your most obedient servant

Chairman

Read:-

(31)

Docket from the Legl Conr Chettaldvoog Desai dated 2nd October 1889 c/o 271/251, stating that a Sum / Rs 2727-7-10 was spent up to the end of the past year on the construc of a Honda (or Pond) in the Municipality of Dawangere, for which a re-revised estimate for Rs 3080 was sanctioned in Pro dated 31st July 1889 c/o 3223-4 and requesting that, 79 as the whole work will have to be completed and the balance of the estimated cost will have to be paid before the end of the current year, the provision in the Budget of Dawangere for the work may be raised from Rs 1000 to Rs 315-2-8-2 the excess amount being

memo
15-xl.

3077
935
2982
2752

3740
935

being met from the accumulated balance of the Municipality, which, the Dy Com^r reports, stood at Rs 6616-3-2 at the beginning of the current year.

Order thereon No 5737-8 of 135 18-10-89/24

The proposed enhancement of the provision of Rs 1000 for the work referred to in the above Rs 315-2-8-2 is sanctioned. When the work is completed, the Dy Com^r is requested to obtain and submit the usual completion report. ~~of the Harbour now under construction at Davangere.~~

The Budget estimates of the Municipality at Davangere as now sanctioned will stand as particularized below.—

below. —

Estimated income

for 1889 90 Rs 3740

Actual balance at the

beginning of the

year — 6616-3-2

Total 10,356-3-2

Expenditure

as already sanctioned

Rs 4890

" now sanction

Rs 2152-8-2

Total Rs 7042-8-2

Closing balance 3,313-11-0

16/11/9

Yours Secretary

To,

The Dy Comr Chittal droog Dist

" Comptroller

B/m

B-137

To the Dy. Comm.r
Chittalong
& Comptroller

Dated 18th Oct. 1889
No 5737-8
135

Sanctioning the
Enhancement of
the provision of Rs 1000
to Rs 8152-8-2. for
the Construction of
a Konda (pond) in
the Municipality of
Sawmpore in the
current years —
municipal Budget.
Draft approved